



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

21106 Kenswick Meadows Ct, Humble, TX 77338, USA

Roof area **2,389 sqft**

Pitch **6:12**

Squares **23.89**



FOOTPRINT 2,539	RIDGE 35 lf	HIP 95 lf	VALLEY 18 lf	RAKE 0 lf	EAVE 155 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$17,080
ITEM	AMOUNT	
Architectural Laminate (26.76 sq, includes 12% waste)	\$3,880	
Tear-off (23.89 sq, 1 layer)	\$836	
Underlayment (25.08 sq)	\$627	
Trim & flashing (drip edge 155 lf, ridge 35 lf, valley 18 lf)	\$1,164	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (5.23 sheets, contingency)	\$287	
Labor (23.89 sq @ 2.85 h/sq)	\$5,797	
Overhead (12%)	\$1,591	
Profit (15%)	\$2,228	
Total	\$17,080	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$14,291

25-yr · 3-tab asphalt

Architectural Laminate

\$17,080

30-yr · architectural laminate

Designer / Impact-Resistant

\$21,247

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,389 sqft of roof area at 6:12 pitch (23.89 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE