



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name
Email
Phone
Prepared by

Property Owner
—
—
Apex Estimator

PROPERTY

21106 Kenswick Meadows Ct, Humble, TX 77338, USA

Roof area
Pitch
Squares

**2,516 sqft
6:12
25.16**



FOOTPRINT
2,250

RIDGE
55 lf

HIP
102 lf

VALLEY
19 lf

RAKE
0 lf

EAVE
187 lf

RECOMMENDED		TOTAL
Architectural Laminate		\$18,201
ITEM	AMOUNT	
Architectural Laminate (28.18 sq, includes 12% waste)	\$4,086	
Tear-off (25.16 sq, 1 layer)	\$881	
Underlayment (26.42 sq)	\$660	
Trim & flashing (drip edge 187 lf, ridge 55 lf, valley 19 lf)	\$1,386	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (5.5 sheets, contingency)	\$303	
Labor (25.16 sq @ 2.87 h/sq)	\$6,146	
Overhead (12%)	\$1,696	
Profit (15%)	\$2,374	
Total	\$18,201	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$15,265

25-yr · 3-tab asphalt

Architectural Laminate

\$18,201

30-yr · architectural laminate

Designer / Impact-Resistant

\$22,590

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,516 sqft of roof area at 6:12 pitch (25.16 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE