



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**3561 E 102nd Ct,
Thornton, CO 80229, USA**

Roof area **1,650 sqft**

Pitch **6:12**

Squares **16.50**



FOOTPRINT 1,476	RIDGE 45 lf	HIP 67.6 lf	VALLEY 18.8 lf	RAKE 0 lf	EAVE 157.8 lf
---------------------------	-----------------------	-----------------------	--------------------------	---------------------	-------------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$12,842
ITEM	AMOUNT	
Architectural Laminate (18.48 sq, includes 12% waste)	\$2,680	
Tear-off (16.5 sq, 1 layer)	\$578	
Underlayment (17.33 sq)	\$433	
Trim & flashing (drip edge 157.8 lf, ridge 45 lf, valley 18.8 lf)	\$1,089	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (3.61 sheets, contingency)	\$199	
Labor (16.5 sq @ 3.08 h/sq)	\$4,323	
Overhead (12%)	\$1,196	
Profit (15%)	\$1,675	
Total	\$12,842	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$10,916

25-yr · 3-tab asphalt

Architectural Laminate

\$12,842

30-yr · architectural laminate

Designer / Impact-Resistant

\$15,720

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 1,650 sqft of roof area at 6:12 pitch (16.50 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE