



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name

Property Owner

Email

—

Phone

—

Prepared by

Apex Estimator

PROPERTY

6310 Laguna Bay Ct,
Houston, TX 77041, USA

Roof area

4,315 sqft

Pitch

5:12

Squares

43.15

FOOTPRINT	RIDGE	HIP	VALLEY	RAKE	EAVE
3,984	39 lf	144 lf	28 lf	12 lf	212 lf

RECOMMENDED		TOTAL
Architectural Laminate		\$28,783
ITEM	AMOUNT	
Architectural Laminate (48.33 sq, includes 12% waste)	\$7,008	
Tear-off (43.15 sq, 1 layer)	\$1,510	
Underlayment (45.31 sq)	\$1,133	
Trim & flashing (drip edge 212 lf, ridge 39 lf, valley 28 lf)	\$1,671	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (9.44 sheets, contingency)	\$519	
Labor (43.15 sq @ 2.68 h/sq)	\$9,837	
Overhead (12%)	\$2,682	
Profit (15%)	\$3,754	
Total	\$28,783	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$23,747

25-yr · 3-tab asphalt

Architectural Laminate

30-yr · architectural laminate

FEATURED

\$28,783

Designer / Impact-Resistant

Lifetime · designer / impact-resistant

\$36,310

Estimate notes. Pricing reflects 4,315 sqft of roof area at 5:12 pitch (43.15 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE