



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**835 S Cobble Creek Blvd,
Nixa, MO 65714, USA**

Roof area **2,753 sqft**

Pitch **6:12**

Squares **27.53**



FOOTPRINT 2,462	RIDGE 34 lf	HIP 111 lf	VALLEY 39 lf	RAKE 8 lf	EAVE 143 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$19,584
ITEM	AMOUNT	
Architectural Laminate (30.83 sq, includes 12% waste)	\$4,471	
Tear-off (27.53 sq, 1 layer)	\$964	
Underlayment (28.91 sq)	\$723	
Trim & flashing (drip edge 143 lf, ridge 34 lf, valley 39 lf)	\$1,376	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.02 sheets, contingency)	\$331	
Labor (27.53 sq @ 2.85 h/sq)	\$6,671	
Overhead (12%)	\$1,825	
Profit (15%)	\$2,554	
Total	\$19,584	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$16,370

25-yr · 3-tab asphalt

Architectural Laminate

\$19,584

30-yr · architectural laminate

Designer / Impact-Resistant

\$24,386

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,753 sqft of roof area at 6:12 pitch (27.53 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE