



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**835 S Cobble Creek Blvd,
Nixa, MO 65714, USA**

Roof area **2,325 sqft**

Pitch **6:12**

Squares **23.25**



FOOTPRINT 2,080	RIDGE 38 lf	HIP 94 lf	VALLEY 22 lf	RAKE 0 lf	EAVE 174 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$16,874
ITEM	AMOUNT	
Architectural Laminate (26.04 sq, includes 12% waste)	\$3,776	
Tear-off (23.25 sq, 1 layer)	\$814	
Underlayment (24.41 sq)	\$610	
Trim & flashing (drip edge 174 lf, ridge 38 lf, valley 22 lf)	\$1,249	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (5.09 sheets, contingency)	\$280	
Labor (23.25 sq @ 2.89 h/sq)	\$5,702	
Overhead (12%)	\$1,572	
Profit (15%)	\$2,201	
Total	\$16,874	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$14,160

25-yr · 3-tab asphalt

Architectural Laminate

\$16,874

30-yr · architectural laminate

Designer / Impact-Resistant

\$20,929

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,325 sqft of roof area at 6:12 pitch (23.25 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE