



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**3561 E 102nd Ct,
Thornton, CO 80229, USA**

Roof area **2,081 sqft**

Pitch **9:12**

Squares **20.81**



FOOTPRINT 2,214	RIDGE 15 lf	HIP 45 lf	VALLEY 0 lf	RAKE 0 lf	EAVE 139 lf
---------------------------	-----------------------	---------------------	-----------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$15,113
ITEM	AMOUNT	
Architectural Laminate (23.31 sq, includes 12% waste)	\$3,380	
Tear-off (20.81 sq, 1 layer)	\$728	
Underlayment (21.85 sq)	\$546	
Trim & flashing (drip edge 139 lf, ridge 15 lf, valley 0 lf)	\$648	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.55 sheets, contingency)	\$250	
Labor (20.81 sq @ 3.12 h/sq)	\$5,512	
Overhead (12%)	\$1,408	
Profit (15%)	\$1,971	
Total	\$15,113	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$12,534

25-yr · 3-tab asphalt

Architectural Laminate

\$15,113

30-yr · architectural laminate

Designer / Impact-Resistant

\$18,893

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 2,081 sqft of roof area at 9:12 pitch (20.81 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE