



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**3561 E 102nd Ct,
Thornton, CO 80229, USA**

Roof area **1,875 sqft**

Pitch **9:12**

Squares **18.75**



FOOTPRINT 1,500	RIDGE 6 lf	HIP 104 lf	VALLEY 0 lf	RAKE 0 lf	EAVE 158 lf
---------------------------	----------------------	----------------------	-----------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$14,213
ITEM	AMOUNT	
Architectural Laminate (21 sq, includes 12% waste)	\$3,045	
Tear-off (18.75 sq, 1 layer)	\$656	
Underlayment (19.69 sq)	\$492	
Trim & flashing (drip edge 158 lf, ridge 6 lf, valley 0 lf)	\$945	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.1 sheets, contingency)	\$226	
Labor (18.75 sq @ 3.14 h/sq)	\$5,001	
Overhead (12%)	\$1,324	
Profit (15%)	\$1,854	
Total	\$14,213	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$11,889

25-yr · 3-tab asphalt

Architectural Laminate

\$14,213

30-yr · architectural laminate

Designer / Impact-Resistant

\$17,619

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 1,875 sqft of roof area at 9:12 pitch (18.75 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE