



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

9381 N Avanyu Dr, Cedar Hills, UT 84062, USA

Roof area **3,658 sqft**

Pitch **6:12**

Squares **36.58**



FOOTPRINT 3,879	RIDGE 34 lf	HIP 105 lf	VALLEY 28 lf	RAKE 0 lf	EAVE 215 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$24,709
ITEM	AMOUNT	
Architectural Laminate (40.97 sq, includes 12% waste)	\$5,941	
Tear-off (36.58 sq, 1 layer)	\$1,280	
Underlayment (38.41 sq)	\$960	
Trim & flashing (drip edge 215 lf, ridge 34 lf, valley 28 lf)	\$1,429	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (8 sheets, contingency)	\$440	
Labor (36.58 sq @ 2.72 h/sq)	\$8,465	
Overhead (12%)	\$2,302	
Profit (15%)	\$3,223	
Total	\$24,709	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$20,440

25-yr · 3-tab asphalt

Architectural Laminate

\$24,709

30-yr · architectural laminate

Designer / Impact-Resistant

\$31,090

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS Fair		2 OBSERVATIONS
Discoloration / staining		LOW · 72%
The north-facing roof slopes are visibly darker in tone compared to the warm brown/tan south-facing slopes. The color differential is stark and consistent across the entire north-facing surface, distinct from shadowing effects. NORTH-FACING SLOPES, UPPER PORTION OF THE MAIN HIP ROOF		
Other		LOW · 98%
A cluster of dark blue/black solar panel arrays is clearly visible, covering a substantial portion of the west-facing slope. Solar panels penetrate the roof membrane with mounting hardware and require flashing at each anchor point — a known potential leak source. WEST-FACING SLOPE, CENTER OF THE MAIN ROOF BODY		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 3,658 sqft of roof area at 6:12 pitch (36.58 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE