



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

5914 Copper Lily, Spring, TX 77389, USA

Roof area **4,369 sqft**

Pitch **6:12**

Squares **43.69**



FOOTPRINT 4,643	RIDGE 51 lf	HIP 121 lf	VALLEY 60 lf	RAKE 14 lf	EAVE 162 lf
---------------------------	-----------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$29,471
ITEM	AMOUNT	
Architectural Laminate (48.93 sq, includes 12% waste)	\$7,095	
Tear-off (43.69 sq, 1 layer)	\$1,529	
Underlayment (45.87 sq)	\$1,147	
Trim & flashing (drip edge 162 lf, ridge 51 lf, valley 60 lf)	\$1,720	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (9.56 sheets, contingency)	\$526	
Labor (43.69 sq @ 2.75 h/sq)	\$10,194	
Overhead (12%)	\$2,746	
Profit (15%)	\$3,844	
Total	\$29,471	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$24,372

25-yr · 3-tab asphalt

Architectural Laminate

\$29,471

30-yr · architectural laminate

Designer / Impact-Resistant

\$37,092

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 4,369 sqft of roof area at 6:12 pitch (43.69 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE