



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

21106 Kenswick Meadows Ct, Humble, TX 77338, USA

Roof area **2,180 sqft**

Pitch **6:12**

Squares **21.80**



FOOTPRINT 1,950	RIDGE 45 lf	HIP 115 lf	VALLEY 22 lf	RAKE 0 lf	EAVE 165 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$16,238
ITEM	AMOUNT	
Architectural Laminate (24.42 sq, includes 12% waste)	\$3,540	
Tear-off (21.8 sq, 1 layer)	\$763	
Underlayment (22.89 sq)	\$572	
Trim & flashing (drip edge 165 lf, ridge 45 lf, valley 22 lf)	\$1,367	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.77 sheets, contingency)	\$262	
Labor (21.8 sq @ 2.93 h/sq)	\$5,433	
Overhead (12%)	\$1,513	
Profit (15%)	\$2,118	
Total	\$16,238	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$13,693

25-yr · 3-tab asphalt

Architectural Laminate

\$16,238

30-yr · architectural laminate

Designer / Impact-Resistant

\$20,040

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,180 sqft of roof area at 6:12 pitch (21.80 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE