



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name
Email
Phone
Prepared by

Property Owner
—
—
Apex Estimator

PROPERTY

5914 Copper Lily, Spring, TX 77389, USA

Roof area
Pitch
Squares

2,467 sqft
6:12
24.67



FOOTPRINT 2,207	RIDGE 51 lf	HIP 229 lf	VALLEY 88 lf	RAKE 0 lf	EAVE 163 lf
--------------------	----------------	---------------	-----------------	--------------	----------------

RECOMMENDED	TOTAL
Architectural Laminate	\$19,787
ITEM	AMOUNT
Architectural Laminate (27.63 sq, includes 12% waste)	\$4,006
Tear-off (24.67 sq, 1 layer)	\$863
Underlayment (25.9 sq)	\$648
Trim & flashing (drip edge 163 lf, ridge 51 lf, valley 88 lf)	\$2,424
Penetrations & vents (boots, chimney, ridge vents)	\$670
Decking allowance (5.4 sheets, contingency)	\$297
Labor (24.67 sq @ 3.08 h/sq)	\$6,455
Overhead (12%)	\$1,844
Profit (15%)	\$2,581
Total	\$19,787

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$16,907

25-yr · 3-tab asphalt

FEATURED

Architectural Laminate

\$19,787

30-yr · architectural laminate

Designer / Impact-Resistant

\$24,090

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,467 sqft of roof area at 6:12 pitch (24.67 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE