



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER


Name
Email
Phone
Prepared by

Property Owner
Apex Estimator

PROPERTY

21106 KENSWICK MEADOWS CT, HUMBLE, TX, 77338

Roof area 3,466 sqft
Pitch 6:12
Squares 34.66



FOOTPRINT
3,100

RIDGE
30 lf

HIP
130 lf

VALLEY
20 lf

RAKE
0 lf

EAVE
155 lf

RECOMMENDED		TOTAL
Architectural Laminate		\$23,403
ITEM	AMOUNT	
Architectural Laminate (38.82 sq, includes 12% waste)	\$5,629	
Tear-off (34.66 sq, 1 layer)	\$1,213	
Underlayment (36.39 sq)	\$910	
Trim & flashing (drip edge 155 lf, ridge 30 lf, valley 20 lf)	\$1,328	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (7.58 sheets, contingency)	\$417	
Labor (34.66 sq @ 2.72 h/sq)	\$8,004	
Overhead (12%)	\$2,180	
Profit (15%)	\$3,053	
Total	\$23,403	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$19,357

25-yr · 3-tab asphalt

Architectural Laminate

\$23,403

30-yr · architectural laminate

Designer / Impact-Resistant

\$29,449

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 3,466 sqft of roof area at 6:12 pitch (34.66 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE