



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name
Email
Phone
Prepared by


Property Owner
—
—
Apex Estimator

PROPERTY

1261 20th St, Newport News, VA 23607, USA

Roof area
Pitch
Squares

**6,118 sqft
6:12
61.18**



FOOTPRINT 6,668	RIDGE 95 lf	HIP 220 lf	VALLEY 65 lf	RAKE 25 lf	EAVE 290 lf
---------------------------	-----------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$41,101
ITEM	AMOUNT	
Architectural Laminate (68.52 sq, includes 12% waste)	\$9,936	
Tear-off (61.18 sq, 1 layer)	\$2,141	
Underlayment (64.24 sq)	\$1,606	
Trim & flashing (drip edge 290 lf, ridge 95 lf, valley 65 lf)	\$2,818	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (13.38 sheets, contingency)	\$736	
Labor (61.18 sq @ 2.69 h/sq)	\$14,004	
Overhead (12%)	\$3,829	
Profit (15%)	\$5,361	
Total	\$41,101	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$33,960

25-yr · 3-tab asphalt

Architectural Laminate

\$41,101

30-yr · architectural laminate

Designer / Impact-Resistant

\$51,772

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS		Fair	2 OBSERVATIONS
Tarp / covering			MEDIUM · 72%
A distinctly teal/green colored rectangular element is visible at the roof edge, clearly contrasting with the surrounding gray asphalt shingle material. It is not consistent with standard roofing material color or texture.			
SOUTH SLOPE, SOUTHEAST CORNER OF THE MAIN STRUCTURE, NEAR THE LOWER ROOF EDGE			
Discoloration / staining			LOW · 60%
A noticeably darker gray patch roughly 8–12 ft in diameter on the central upper roof plane, distinct in tone from the surrounding uniform gray shingles.			
UPPER MAIN ROOF SECTION, NEAR THE CENTER RIDGE AREA			
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS			

Estimate notes. Pricing reflects 6,118 sqft of roof area at 6:12 pitch (61.18 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE