



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

14132 Trenton Ave, Orland Park, IL 60462, USA

Roof area **3,170 sqft**

Pitch **5:12**

Squares **31.70**



FOOTPRINT 3,349	RIDGE 25 lf	HIP 105 lf	VALLEY 26 lf	RAKE 0 lf	EAVE 222 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$21,818
ITEM	AMOUNT	
Architectural Laminate (35.5 sq, includes 12% waste)	\$5,148	
Tear-off (31.7 sq, 1 layer)	\$1,110	
Underlayment (33.29 sq)	\$832	
Trim & flashing (drip edge 222 lf, ridge 25 lf, valley 26 lf)	\$1,387	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.93 sheets, contingency)	\$381	
Labor (31.7 sq @ 2.75 h/sq)	\$7,411	
Overhead (12%)	\$2,033	
Profit (15%)	\$2,846	
Total	\$21,818	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$18,118

25-yr · 3-tab asphalt

Architectural Laminate

\$21,818

30-yr · architectural laminate

Designer / Impact-Resistant

\$27,347

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS Fair		1 OBSERVATION
Other A bright white rectangular object, approximately 4–6 ft in its longest dimension, is visible on the north-facing slope near the peak. It is clearly distinct in color and texture from the surrounding tan/beige shingles and does not match any other rooftop element on this roof. NORTH SLOPE, NEAR THE RIDGE, CENTER OF THE ROOF.		MEDIUM · 70%
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 3,170 sqft of roof area at 5:12 pitch (31.70 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE