



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

5914 Copper Lily, Spring, TX 77389, USA

Roof area **4,369 sqft**

Pitch **6:12**

Squares **43.69**



FOOTPRINT 4,643	RIDGE 31 lf	HIP 104 lf	VALLEY 56 lf	RAKE 8 lf	EAVE 161 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$29,037
ITEM	AMOUNT	
Architectural Laminate (48.93 sq, includes 12% waste)	\$7,095	
Tear-off (43.69 sq, 1 layer)	\$1,529	
Underlayment (45.87 sq)	\$1,147	
Trim & flashing (drip edge 161 lf, ridge 31 lf, valley 56 lf)	\$1,490	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (9.56 sheets, contingency)	\$526	
Labor (43.69 sq @ 2.72 h/sq)	\$10,088	
Overhead (12%)	\$2,705	
Profit (15%)	\$3,787	
Total	\$29,037	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$23,937

25-yr · 3-tab asphalt

Architectural Laminate

\$29,037

30-yr · architectural laminate

Designer / Impact-Resistant

\$36,657

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 4,369 sqft of roof area at 6:12 pitch (43.69 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE