



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**835 S Cobble Creek Blvd,
Nixa, MO 65714, USA**

Roof area **3,287 sqft**

Pitch **6:12**

Squares **32.87**



FOOTPRINT 2,940	RIDGE 35 lf	HIP 133 lf	VALLEY 51 lf	RAKE 0 lf	EAVE 264 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$23,340
ITEM	AMOUNT	
Architectural Laminate (36.81 sq, includes 12% waste)	\$5,338	
Tear-off (32.87 sq, 1 layer)	\$1,150	
Underlayment (34.51 sq)	\$863	
Trim & flashing (drip edge 264 lf, ridge 35 lf, valley 51 lf)	\$1,857	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (7.19 sheets, contingency)	\$395	
Labor (32.87 sq @ 2.81 h/sq)	\$7,847	
Overhead (12%)	\$2,175	
Profit (15%)	\$3,044	
Total	\$23,340	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$19,503

25-yr · 3-tab asphalt

Architectural Laminate

\$23,340

30-yr · architectural laminate

Designer / Impact-Resistant

\$29,074

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 3,287 sqft of roof area at 6:12 pitch (32.87 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE