



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**835 S Cobble Creek Blvd,
Nixa, MO 65714, USA**

Roof area **2,009 sqft**

Pitch **6:12**

Squares **20.09**



FOOTPRINT 1,797	RIDGE 27 lf	HIP 88 lf	VALLEY 21 lf	RAKE 5 lf	EAVE 96 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$14,657
ITEM	AMOUNT	
Architectural Laminate (22.5 sq, includes 12% waste)	\$3,263	
Tear-off (20.09 sq, 1 layer)	\$703	
Underlayment (21.09 sq)	\$527	
Trim & flashing (drip edge 96 lf, ridge 27 lf, valley 21 lf)	\$975	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.39 sheets, contingency)	\$242	
Labor (20.09 sq @ 2.93 h/sq)	\$5,001	
Overhead (12%)	\$1,366	
Profit (15%)	\$1,912	
Total	\$14,657	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$12,312

25-yr · 3-tab asphalt

Architectural Laminate

\$14,657

30-yr · architectural laminate

Designer / Impact-Resistant

\$18,162

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,009 sqft of roof area at 6:12 pitch (20.09 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE