



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**1457 Garden View Ct,
Saratoga Springs, UT
84045, USA**

Roof area **4,090 sqft**

Pitch **6:12**

Squares **40.90**



FOOTPRINT 4,914	RIDGE 31.7 lf	HIP 84 lf	VALLEY 20.5 lf	RAKE 0 lf	EAVE 142 lf
---------------------------	-------------------------	---------------------	--------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$26,641
ITEM	AMOUNT	
Architectural Laminate (45.81 sq, includes 12% waste)	\$6,642	
Tear-off (40.9 sq, 1 layer)	\$1,432	
Underlayment (42.95 sq)	\$1,074	
Trim & flashing (drip edge 142 lf, ridge 31.7 lf, valley 20.5 lf)	\$1,077	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (8.95 sheets, contingency)	\$492	
Labor (40.9 sq @ 2.67 h/sq)	\$9,297	
Overhead (12%)	\$2,482	
Profit (15%)	\$3,475	
Total	\$26,641	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$21,867

25-yr · 3-tab asphalt

Architectural Laminate

\$26,641

30-yr · architectural laminate

Designer / Impact-Resistant

\$33,775

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 4,090 sqft of roof area at 6:12 pitch (40.90 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE