



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

5914 Copper Lily, Spring, TX 77389, USA

Roof area **4,369 sqft**

Pitch **6:12**

Squares **43.69**



FOOTPRINT 4,643	RIDGE 46 lf	HIP 112 lf	VALLEY 50 lf	RAKE 25 lf	EAVE 100 lf
---------------------------	-----------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$29,021
ITEM	AMOUNT	
Architectural Laminate (48.93 sq, includes 12% waste)	\$7,095	
Tear-off (43.69 sq, 1 layer)	\$1,529	
Underlayment (45.87 sq)	\$1,147	
Trim & flashing (drip edge 100 lf, ridge 46 lf, valley 50 lf)	\$1,453	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (9.56 sheets, contingency)	\$526	
Labor (43.69 sq @ 2.72 h/sq)	\$10,112	
Overhead (12%)	\$2,704	
Profit (15%)	\$3,785	
Total	\$29,021	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$23,921

25-yr · 3-tab asphalt

Architectural Laminate

\$29,021

30-yr · architectural laminate

Designer / Impact-Resistant

\$36,641

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 4,369 sqft of roof area at 6:12 pitch (43.69 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE