



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

122 NW 13th Ave, Cape Coral, FL 33993, USA

Roof area **2,924 sqft**

Pitch **6:12**

Squares **29.24**



FOOTPRINT 3,020	RIDGE 38 lf	HIP 68 lf	VALLEY 30 lf	RAKE 0 lf	EAVE 185 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$20,283
ITEM	AMOUNT	
Architectural Laminate (32.75 sq, includes 12% waste)	\$4,749	
Tear-off (29.24 sq, 1 layer)	\$1,023	
Underlayment (30.7 sq)	\$768	
Trim & flashing (drip edge 185 lf, ridge 38 lf, valley 30 lf)	\$1,203	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.4 sheets, contingency)	\$352	
Labor (29.24 sq @ 2.81 h/sq)	\$6,984	
Overhead (12%)	\$1,890	
Profit (15%)	\$2,646	
Total	\$20,283	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$16,870

25-yr · 3-tab asphalt

Architectural Laminate

\$20,283

30-yr · architectural laminate

Designer / Impact-Resistant

\$25,383

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS Concerning		2 OBSERVATIONS
Tarp / covering Bright blue tarps cover the entire main roof surface — both the primary hip roof section and the lower secondary roof section (likely garage or addition). The tarps are large, uniform blue in color, and span all visible slopes with no underlying shingle material visible beneath them. WHOLE ROOF — ALL SLOPES OF BOTH THE MAIN STRUCTURE AND THE LOWER ATTACHED SECTION		HIGH · 100%
Tarp / covering A lighter blue-white section of tarp on the lower-front (south-facing) slope is visually distinct from the darker blue tarps on the upper sections, indicating a separate, overlapping tarp layer or partial underlayment exposure. SOUTH SLOPE OF THE LOWER ATTACHED ROOF SECTION, CENTER TO RIGHT HALF		HIGH · 90%
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 2,924 sqft of roof area at 6:12 pitch (29.24 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE