



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

21106 Kenswick Meadows Ct, Humble, TX 77338, USA

Roof area **2,389 sqft**

Pitch **7:12**

Squares **23.89**



FOOTPRINT 2,539	RIDGE 35 lf	HIP 75 lf	VALLEY 19 lf	RAKE 10 lf	EAVE 124 lf
---------------------------	-----------------------	---------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$16,900
ITEM	AMOUNT	
Architectural Laminate (26.76 sq, includes 12% waste)	\$3,880	
Tear-off (23.89 sq, 1 layer)	\$836	
Underlayment (25.08 sq)	\$627	
Trim & flashing (drip edge 124 lf, ridge 35 lf, valley 19 lf)	\$1,018	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (5.23 sheets, contingency)	\$287	
Labor (23.89 sq @ 2.86 h/sq)	\$5,803	
Overhead (12%)	\$1,575	
Profit (15%)	\$2,204	
Total	\$16,900	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$14,112

25-yr · 3-tab asphalt

Architectural Laminate

\$16,900

30-yr · architectural laminate

Designer / Impact-Resistant

\$21,067

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS Concerning		3 OBSERVATIONS
	Other	MEDIUM · 85%
	Large flat-roof section with a bright white/light gray surface that is distinctly different in material and color from every neighboring home's dark gray shingle roofing, consistent with a flat-roof membrane (TPO/EPDM) or exposed roof decking during active construction. CENTRAL AND LOWER PORTIONS OF THE SUBJECT ROOF, ENCOMPASSING THE MAJORITY OF THE AREA WITHIN THE BOUNDING BOX.	
	Debris	MEDIUM · 72%
	Multiple small scattered dark objects (approximately 8–12 distinct spots) distributed across the light-colored flat roof surface, irregular spacing, inconsistent with rooftop mechanical equipment. ACROSS THE FLAT CENTRAL ROOF SECTION, DISTRIBUTED FROM MID-ROOF TOWARD THE SOUTH SLOPE.	
	Debris	HIGH · 92%
	Large piles of dimensional lumber and construction materials (tan/yellow in color) stacked directly adjacent to the east and southeast roof edges, with some material appearing to lean against or rest at the roof perimeter. EAST AND SOUTHEAST PERIMETER OF THE SUBJECT ROOF/STRUCTURE.	
	AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS	

Estimate notes. Pricing reflects 2,389 sqft of roof area at 7:12 pitch (23.89 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE	APEX AUTHORIZED · DATE
--	---

Apex Roofing & Exteriors · (xxx) xxx-xxxx · estimates@apexroofing.example

Powered by JobNimbus