



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**3820 E Rosebrier St,
Springfield, MO 65809,
USA**

Roof area **6,015 sqft**

Pitch **6:12**

Squares **60.15**



FOOTPRINT 5,380	RIDGE 103 lf	HIP 189 lf	VALLEY 59 lf	RAKE 13 lf	EAVE 223 lf
---------------------------	------------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$40,053
ITEM	AMOUNT	
Architectural Laminate (67.37 sq, includes 12% waste)	\$9,768	
Tear-off (60.15 sq, 1 layer)	\$2,105	
Underlayment (63.16 sq)	\$1,579	
Trim & flashing (drip edge 223 lf, ridge 103 lf, valley 59 lf)	\$2,463	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (13.16 sheets, contingency)	\$724	
Labor (60.15 sq @ 2.70 h/sq)	\$13,788	
Overhead (12%)	\$3,732	
Profit (15%)	\$5,224	
Total	\$40,053	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$33,032

25-yr · 3-tab asphalt

Architectural Laminate

\$40,053

30-yr · architectural laminate

Designer / Impact-Resistant

\$50,545

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS		Fair	2 OBSERVATIONS
Discoloration / staining			LOW · 75%
A large, distinctly lighter tan/beige roof section occupies the north and northwest portions of the roof, contrasting sharply with the darker brown shingle sections on the south and southwest slopes. The color boundary is abrupt and consistent across a broad area, not attributable to shadow.			
NORTH AND NORTHWEST ROOF SECTIONS, UPPER/FRONT PORTION OF THE HOME			
Visible patching			LOW · 70%
The lighter-colored northern section exhibits a flat or very low-slope profile compared to the clearly pitched darker sections. The material texture visible differs from the surrounding steep-slope shingle areas, indicating a different roofing material on this section (consistent with modified bitumen or TPO on a low-slope area).			
NORTH-FACING LOW-SLOPE SECTION, CENTRAL-NORTH PORTION OF ROOF			
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS			

Estimate notes. Pricing reflects 6,015 sqft of roof area at 6:12 pitch (60.15 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE