



# Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**6310 Laguna Bay Ct,  
Houston, TX 77041, USA**

Roof area **4,186 sqft**

Pitch **8:12**

Squares **41.86**



|                           |                       |                      |                        |                      |                       |
|---------------------------|-----------------------|----------------------|------------------------|----------------------|-----------------------|
| FOOTPRINT<br><b>4,359</b> | RIDGE<br><b>39 lf</b> | HIP<br><b>144 lf</b> | VALLEY<br><b>28 lf</b> | RAKE<br><b>12 lf</b> | EAVE<br><b>212 lf</b> |
|---------------------------|-----------------------|----------------------|------------------------|----------------------|-----------------------|

| RECOMMENDED                                                   |                 | TOTAL           |
|---------------------------------------------------------------|-----------------|-----------------|
| Architectural Laminate                                        |                 | <b>\$29,395</b> |
| ITEM                                                          | AMOUNT          |                 |
| Architectural Laminate (46.88 sq, includes 12% waste)         | \$6,798         |                 |
| Tear-off (41.86 sq, 1 layer)                                  | \$1,465         |                 |
| Underlayment (43.95 sq)                                       | \$1,099         |                 |
| Trim & flashing (drip edge 212 lf, ridge 39 lf, valley 28 lf) | \$1,671         |                 |
| Penetrations & vents (boots, chimney, ridge vents)            | \$670           |                 |
| Decking allowance (9.16 sheets, contingency)                  | \$504           |                 |
| Labor (41.86 sq @ 2.98 h/sq)                                  | \$10,615        |                 |
| Overhead (12%)                                                | \$2,739         |                 |
| Profit (15%)                                                  | \$3,834         |                 |
| Total                                                         | <b>\$29,395</b> |                 |

COMPARE OPTIONS

**3-Tab Asphalt Shingle**

**\$24,206**

25-yr · 3-tab asphalt

**Architectural Laminate**

**\$29,395**

30-yr · architectural laminate

**Designer / Impact-Resistant**

**\$36,999**

Lifetime · designer / impact-resistant

| PRE-INSPECTION OBSERVATIONS <b>Fair</b>                                                                                                                                                                                                                                                                                                                                                                                                             |  | 1 OBSERVATION |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|---------------|
| <b>Other</b><br>A distinctly lighter tan/gray flat or low-slope roof section is visible in the center of the roof complex, clearly contrasting in both color and texture from the surrounding dark gray hip-roof shingle sections. This section spans approximately 15–20 ft and uses a visibly different roofing material (consistent with modified bitumen or TPO).<br>CENTER OF SUBJECT ROOF, BETWEEN THE NORTHERN AND SOUTHERN HIP-ROOF VOLUMES |  | LOW · 82%     |
| AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS                                                                                                                                                                                                                                                                                                                                                                              |  |               |

**Estimate notes.** Pricing reflects 4,186 sqft of roof area at 8:12 pitch (41.86 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

**Warranty:** tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE