



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**835 S Cobble Creek Blvd,
Nixa, MO 65714, USA**

Roof area **3,070 sqft**

Pitch **8:12**

Squares **30.70**



FOOTPRINT 3,254	RIDGE 35 lf	HIP 133 lf	VALLEY 51 lf	RAKE 0 lf	EAVE 264 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$23,147
ITEM	AMOUNT	
Architectural Laminate (34.38 sq, includes 12% waste)	\$4,986	
Tear-off (30.7 sq, 1 layer)	\$1,075	
Underlayment (32.24 sq)	\$806	
Trim & flashing (drip edge 264 lf, ridge 35 lf, valley 51 lf)	\$1,857	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.72 sheets, contingency)	\$369	
Labor (30.7 sq @ 3.15 h/sq)	\$8,208	
Overhead (12%)	\$2,157	
Profit (15%)	\$3,019	
Total	\$23,147	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$19,341

25-yr · 3-tab asphalt

Architectural Laminate

\$23,147

30-yr · architectural laminate

Designer / Impact-Resistant

\$28,723

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 3,070 sqft of roof area at 8:12 pitch (30.70 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE