



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**10046 Riverside Ln,
Highland, UT 84003, USA**

Roof area **3,793 sqft**

Pitch **7:12**

Squares **37.93**



FOOTPRINT 4,289	RIDGE 96 lf	HIP 117 lf	VALLEY 63 lf	RAKE 76 lf	EAVE 155 lf
---------------------------	-----------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$26,927
ITEM	AMOUNT	
Architectural Laminate (42.48 sq, includes 12% waste)	\$6,160	
Tear-off (37.93 sq, 1 layer)	\$1,328	
Underlayment (39.83 sq)	\$996	
Trim & flashing (drip edge 155 lf, ridge 96 lf, valley 63 lf)	\$2,084	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (8.3 sheets, contingency)	\$456	
Labor (37.93 sq @ 2.86 h/sq)	\$9,213	
Overhead (12%)	\$2,509	
Profit (15%)	\$3,512	
Total	\$26,927	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$22,500

25-yr · 3-tab asphalt

Architectural Laminate

\$26,927

30-yr · architectural laminate

Designer / Impact-Resistant

\$33,543

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 3,793 sqft of roof area at 7:12 pitch (37.93 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE