



# Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**21106 Kenswick Meadows Ct, Humble, TX 77338, USA**

Roof area **2,389 sqft**

Pitch **6:12**

Squares **23.89**



|                           |                       |                     |                        |                     |                       |
|---------------------------|-----------------------|---------------------|------------------------|---------------------|-----------------------|
| FOOTPRINT<br><b>2,539</b> | RIDGE<br><b>20 lf</b> | HIP<br><b>70 lf</b> | VALLEY<br><b>18 lf</b> | RAKE<br><b>5 lf</b> | EAVE<br><b>130 lf</b> |
|---------------------------|-----------------------|---------------------|------------------------|---------------------|-----------------------|

| RECOMMENDED                                                   |                 | TOTAL           |
|---------------------------------------------------------------|-----------------|-----------------|
| Architectural Laminate                                        |                 | <b>\$16,678</b> |
| ITEM                                                          | AMOUNT          |                 |
| Architectural Laminate (26.76 sq, includes 12% waste)         | \$3,880         |                 |
| Tear-off (23.89 sq, 1 layer)                                  | \$836           |                 |
| Underlayment (25.08 sq)                                       | \$627           |                 |
| Trim & flashing (drip edge 130 lf, ridge 20 lf, valley 18 lf) | \$914           |                 |
| Penetrations & vents (boots, chimney, ridge vents)            | \$670           |                 |
| Decking allowance (5.23 sheets, contingency)                  | \$287           |                 |
| Labor (23.89 sq @ 2.82 h/sq)                                  | \$5,735         |                 |
| Overhead (12%)                                                | \$1,554         |                 |
| Profit (15%)                                                  | \$2,175         |                 |
| Total                                                         | <b>\$16,678</b> |                 |

COMPARE OPTIONS

3-Tab Asphalt Shingle

**\$13,890**

25-yr · 3-tab asphalt

Architectural Laminate

**\$16,678**

30-yr · architectural laminate

Designer / Impact-Resistant

**\$20,845**

Lifetime · designer / impact-resistant

| PRE-INSPECTION OBSERVATIONS <b>Fair</b>                                                                                                                                                                                                                                                                                                                              |  | 2 OBSERVATIONS |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------|
| <b>Discoloration / staining</b>                                                                                                                                                                                                                                                                                                                                      |  | LOW · 80%      |
| The entire main roof slope within the bounding box is a uniformly light off-white/pale gray color, starkly different from the dark charcoal-gray shingles on every neighboring home visible in the image. The contrast is sharp and consistent across the full slope surface.<br>PRIMARY SOUTH-FACING ROOF SLOPE, FULL EXTENT VISIBLE WITHIN THE ORANGE BOUNDING BOX |  |                |
| <b>Debris</b>                                                                                                                                                                                                                                                                                                                                                        |  | LOW · 90%      |
| Multiple stacks of lumber/construction material are visible lying flat on the ground immediately adjacent to and around the roof perimeter — tan/yellow linear objects arranged in loose piles on the east and south sides of the structure.<br>GROUND-LEVEL PERIMETER ON THE EAST AND SOUTH SIDES OF THE SUBJECT STRUCTURE                                          |  |                |
| AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS                                                                                                                                                                                                                                                                                               |  |                |

**Estimate notes.** Pricing reflects 2,389 sqft of roof area at 6:12 pitch (23.89 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

**Warranty:** tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE