



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**3561 E 102nd Ct,
Thornton, CO 80229, USA**

Roof area **2,081 sqft**

Pitch **9:12**

Squares **20.81**



FOOTPRINT 2,214	RIDGE 19 lf	HIP 88 lf	VALLEY 0 lf	RAKE 0 lf	EAVE 166 lf
---------------------------	-----------------------	---------------------	-----------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$15,526
ITEM	AMOUNT	
Architectural Laminate (23.31 sq, includes 12% waste)	\$3,380	
Tear-off (20.81 sq, 1 layer)	\$728	
Underlayment (21.85 sq)	\$546	
Trim & flashing (drip edge 166 lf, ridge 19 lf, valley 0 lf)	\$950	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.55 sheets, contingency)	\$250	
Labor (20.81 sq @ 3.13 h/sq)	\$5,530	
Overhead (12%)	\$1,447	
Profit (15%)	\$2,025	
Total	\$15,526	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$12,947

25-yr · 3-tab asphalt

Architectural Laminate

\$15,526

30-yr · architectural laminate

Designer / Impact-Resistant

\$19,307

Lifetime · designer / impact-resistant

PRE-INSPECTION OBSERVATIONS	Good	0 OBSERVATIONS
No notable issues visible from satellite imagery. An in-person inspection will confirm.		
AI VISION CONDITION ASSESSMENT · PRE-INSPECTION ONLY · NOT A DIAGNOSIS		

Estimate notes. Pricing reflects 2,081 sqft of roof area at 9:12 pitch (20.81 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.

Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE