



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

1261 20th St, Newport News, VA 23607, USA

Roof area **4,025 sqft**

Pitch **6:12**

Squares **40.25**



FOOTPRINT 3,600	RIDGE 67 lf	HIP 254 lf	VALLEY 50 lf	RAKE 0 lf	EAVE 176 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$28,390
ITEM	AMOUNT	
Architectural Laminate (45.08 sq, includes 12% waste)	\$6,537	
Tear-off (40.25 sq, 1 layer)	\$1,409	
Underlayment (42.26 sq)	\$1,057	
Trim & flashing (drip edge 176 lf, ridge 67 lf, valley 50 lf)	\$2,395	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (8.8 sheets, contingency)	\$484	
Labor (40.25 sq @ 2.77 h/sq)	\$9,491	
Overhead (12%)	\$2,645	
Profit (15%)	\$3,703	
Total	\$28,390	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$23,692

25-yr · 3-tab asphalt

Architectural Laminate

\$28,390

30-yr · architectural laminate

Designer / Impact-Resistant

\$35,411

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 4,025 sqft of roof area at 6:12 pitch (40.25 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE