



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**1612 S Canton Ave,
Springfield, MO 65802,
USA**

Roof area **3,179 sqft**

Pitch **5:12**

Squares **31.79**



FOOTPRINT 2,935	RIDGE 49.7 lf	HIP 121 lf	VALLEY 22.4 lf	RAKE 4.9 lf	EAVE 197.1 lf
---------------------------	-------------------------	----------------------	--------------------------	-----------------------	-------------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$22,137
ITEM	AMOUNT	
Architectural Laminate (35.6 sq, includes 12% waste)	\$5,163	
Tear-off (31.79 sq, 1 layer)	\$1,113	
Underlayment (33.38 sq)	\$834	
Trim & flashing (drip edge 197.1 lf, ridge 49.7 lf, valley 22.4 lf)	\$1,515	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.95 sheets, contingency)	\$382	
Labor (31.79 sq @ 2.78 h/sq)	\$7,509	
Overhead (12%)	\$2,062	
Profit (15%)	\$2,887	
Total	\$22,137	

COMPARE OPTIONS

3-Tab Asphalt Shingle \$18,426 25-yr · 3-tab asphalt	Architectural Laminate \$22,137 30-yr · architectural laminate	Designer / Impact-Resistant \$27,682 Lifetime · designer / impact-resistant
--	--	---

Estimate notes. Pricing reflects 3,179 sqft of roof area at 5:12 pitch (31.79 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE