



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**3820 E Rosebrier St,
Springfield, MO 65809,
USA**

Roof area **4,102 sqft**

Pitch **6:12**

Squares **41.02**



FOOTPRINT
3,669

RIDGE
95 lf

HIP
183 lf

VALLEY
78 lf

RAKE
0 lf

EAVE
279 lf

RECOMMENDED		TOTAL
Architectural Laminate		\$29,506
ITEM	AMOUNT	
Architectural Laminate (45.94 sq, includes 12% waste)	\$6,662	
Tear-off (41.02 sq, 1 layer)	\$1,436	
Underlayment (43.07 sq)	\$1,077	
Trim & flashing (drip edge 279 lf, ridge 95 lf, valley 78 lf)	\$2,634	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (8.97 sheets, contingency)	\$494	
Labor (41.02 sq @ 2.85 h/sq)	\$9,937	
Overhead (12%)	\$2,749	
Profit (15%)	\$3,849	
Total	\$29,506	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$24,718

25-yr · 3-tab asphalt

Architectural Laminate

\$29,506

30-yr · architectural laminate

Designer / Impact-Resistant

\$36,661

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 4,102 sqft of roof area at 6:12 pitch (41.02 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE