



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**6310 Laguna Bay Ct,
Houston, TX 77041, USA**

Roof area **3,414 sqft**

Pitch **5:12**

Squares **34.14**



FOOTPRINT 3,152	RIDGE 63 lf	HIP 193 lf	VALLEY 57 lf	RAKE 0 lf	EAVE 170 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$24,576
ITEM	AMOUNT	
Architectural Laminate (38.24 sq, includes 12% waste)	\$5,544	
Tear-off (34.14 sq, 1 layer)	\$1,195	
Underlayment (35.85 sq)	\$896	
Trim & flashing (drip edge 170 lf, ridge 63 lf, valley 57 lf)	\$2,104	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (7.47 sheets, contingency)	\$411	
Labor (34.14 sq @ 2.85 h/sq)	\$8,261	
Overhead (12%)	\$2,290	
Profit (15%)	\$3,206	
Total	\$24,576	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$20,591

25-yr · 3-tab asphalt

Architectural Laminate

\$24,576

30-yr · architectural laminate

Designer / Impact-Resistant

\$30,531

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 3,414 sqft of roof area at 5:12 pitch (34.14 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE