



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

122 NW 13th Ave, Cape Coral, FL 33993, USA

Roof area **2,924 sqft**

Pitch **4:12**

Squares **29.24**



FOOTPRINT 3,020	RIDGE 38 lf	HIP 68 lf	VALLEY 30 lf	RAKE 0 lf	EAVE 185 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$19,465
ITEM	AMOUNT	
Architectural Laminate (32.75 sq, includes 12% waste)	\$4,749	
Tear-off (29.24 sq, 1 layer)	\$1,023	
Underlayment (30.7 sq)	\$768	
Trim & flashing (drip edge 185 lf, ridge 38 lf, valley 30 lf)	\$1,203	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.4 sheets, contingency)	\$352	
Labor (29.24 sq @ 2.55 h/sq)	\$6,349	
Overhead (12%)	\$1,814	
Profit (15%)	\$2,539	
Total	\$19,465	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$16,228

25-yr · 3-tab asphalt

Architectural Laminate

\$19,465

30-yr · architectural laminate

Designer / Impact-Resistant

\$24,389

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,924 sqft of roof area at 4:12 pitch (29.24 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE