



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name

Email

Phone

Prepared by

Property Owner

—

—

Apex Estimator

PROPERTY

1261 20th St, Newport News, VA 23607, USA

Roof area


Pitch

Squares

6,118 sqft

6:12

61.18



FOOTPRINT

6,668

RIDGE

95 lf

HIP

220 lf

VALLEY

65 lf

RAKE

25 lf

EAVE

290 lf

RECOMMENDED		TOTAL
Architectural Laminate		\$41,101
ITEM	AMOUNT	
Architectural Laminate (68.52 sq, includes 12% waste)	\$9,936	
Tear-off (61.18 sq, 1 layer)	\$2,141	
Underlayment (64.24 sq)	\$1,606	
Trim & flashing (drip edge 290 lf, ridge 95 lf, valley 65 lf)	\$2,818	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (13.38 sheets, contingency)	\$736	
Labor (61.18 sq @ 2.69 h/sq)	\$14,004	
Overhead (12%)	\$3,829	
Profit (15%)	\$5,361	
Total	\$41,101	

COMPARE OPTIONS

3-Tab Asphalt Shingle \$33,960 25-yr · 3-tab asphalt	Architectural Laminate \$41,101 30-yr · architectural laminate	Designer / Impact-Resistant \$51,772 Lifetime · designer / impact-resistant
--	--	---

Estimate notes. Pricing reflects 6,118 sqft of roof area at 6:12 pitch (61.18 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE