



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**


PROPERTY

**1612 S Canton Ave,
Springfield, MO 65802,
USA**

Roof area **2,757 sqft**

Pitch **5:12**

Squares **27.57**



FOOTPRINT 2,828	RIDGE 39 lf	HIP 109 lf	VALLEY 28 lf	RAKE 0 lf	EAVE 154 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$19,475
ITEM	AMOUNT	
Architectural Laminate (30.88 sq, includes 12% waste)	\$4,477	
Tear-off (27.57 sq, 1 layer)	\$965	
Underlayment (28.95 sq)	\$724	
Trim & flashing (drip edge 154 lf, ridge 39 lf, valley 28 lf)	\$1,321	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.03 sheets, contingency)	\$332	
Labor (27.57 sq @ 2.83 h/sq)	\$6,632	
Overhead (12%)	\$1,814	
Profit (15%)	\$2,540	
Total	\$19,475	

COMPARE OPTIONS

3-Tab Asphalt Shingle \$16,257 25-yr · 3-tab asphalt	Architectural Laminate \$19,475 30-yr · architectural laminate	Designer / Impact-Resistant \$24,284 Lifetime · designer / impact-resistant
--	--	---

Estimate notes. Pricing reflects 2,757 sqft of roof area at 5:12 pitch (27.57 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE