



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**6310 Laguna Bay Ct,
Houston, TX 77041, USA**

Roof area **4,315 sqft**

Pitch **5:12**

Squares **43.15**



FOOTPRINT 3,984	RIDGE 39 lf	HIP 144 lf	VALLEY 28 lf	RAKE 12 lf	EAVE 212 lf
---------------------------	-----------------------	----------------------	------------------------	----------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$28,783
ITEM	AMOUNT	
Architectural Laminate (48.33 sq, includes 12% waste)	\$7,008	
Tear-off (43.15 sq, 1 layer)	\$1,510	
Underlayment (45.31 sq)	\$1,133	
Trim & flashing (drip edge 212 lf, ridge 39 lf, valley 28 lf)	\$1,671	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (9.44 sheets, contingency)	\$519	
Labor (43.15 sq @ 2.68 h/sq)	\$9,837	
Overhead (12%)	\$2,682	
Profit (15%)	\$3,754	
Total	\$28,783	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$23,747

25-yr · 3-tab asphalt

Architectural Laminate

\$28,783

30-yr · architectural laminate

Designer / Impact-Resistant

\$36,310

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 4,315 sqft of roof area at 5:12 pitch (43.15 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE