



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

**3561 E 102nd Ct,
Thornton, CO 80229, USA**

Roof area **1,971 sqft**

Pitch **5:12**

Squares **19.71**



FOOTPRINT 1,820	RIDGE 25 lf	HIP 83 lf	VALLEY 19 lf	RAKE 0 lf	EAVE 160 lf
---------------------------	-----------------------	---------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$14,542
ITEM	AMOUNT	
Architectural Laminate (22.08 sq, includes 12% waste)	\$3,201	
Tear-off (19.71 sq, 1 layer)	\$690	
Underlayment (20.7 sq)	\$517	
Trim & flashing (drip edge 160 lf, ridge 25 lf, valley 19 lf)	\$1,073	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (4.31 sheets, contingency)	\$237	
Labor (19.71 sq @ 2.93 h/sq)	\$4,902	
Overhead (12%)	\$1,355	
Profit (15%)	\$1,897	
Total	\$14,542	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$12,241

25-yr · 3-tab asphalt

Architectural Laminate

\$14,542

30-yr · architectural laminate

Designer / Impact-Resistant

\$17,980

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 1,971 sqft of roof area at 5:12 pitch (19.71 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE