



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

5914 Copper Lily, Spring, TX 77389, USA

Roof area **2,524 sqft**

Pitch **6:12**

Squares **25.24**



FOOTPRINT 2,258	RIDGE 40 lf	HIP 172 lf	VALLEY 56 lf	RAKE 0 lf	EAVE 87 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$18,827
ITEM	AMOUNT	
Architectural Laminate (28.27 sq, includes 12% waste)	\$4,099	
Tear-off (25.24 sq, 1 layer)	\$883	
Underlayment (26.5 sq)	\$663	
Trim & flashing (drip edge 87 lf, ridge 40 lf, valley 56 lf)	\$1,670	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (5.52 sheets, contingency)	\$304	
Labor (25.24 sq @ 2.95 h/sq)	\$6,329	
Overhead (12%)	\$1,754	
Profit (15%)	\$2,456	
Total	\$18,827	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$15,881

25-yr · 3-tab asphalt

Architectural Laminate

\$18,827

30-yr · architectural laminate

Designer / Impact-Resistant

\$23,230

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 2,524 sqft of roof area at 6:12 pitch (25.24 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE