



Roof Replacement Estimate

Prepared for Property Owner · Three options for your home

CUSTOMER

Name **Property Owner**

Email **—**

Phone **—**

Prepared by **Apex Estimator**

PROPERTY

122 NW 13th Ave, Cape Coral, FL 33993, USA

Roof area **3,057 sqft**

Pitch **4:12**

Squares **30.57**



FOOTPRINT 2,900	RIDGE 35 lf	HIP 112 lf	VALLEY 37 lf	RAKE 0 lf	EAVE 210 lf
---------------------------	-----------------------	----------------------	------------------------	---------------------	-----------------------

RECOMMENDED		TOTAL
Architectural Laminate		\$20,633
ITEM	AMOUNT	
Architectural Laminate (34.24 sq, includes 12% waste)	\$4,965	
Tear-off (30.57 sq, 1 layer)	\$1,070	
Underlayment (32.1 sq)	\$802	
Trim & flashing (drip edge 210 lf, ridge 35 lf, valley 37 lf)	\$1,519	
Penetrations & vents (boots, chimney, ridge vents)	\$670	
Decking allowance (6.69 sheets, contingency)	\$368	
Labor (30.57 sq @ 2.55 h/sq)	\$6,625	
Overhead (12%)	\$1,922	
Profit (15%)	\$2,691	
Total	\$20,633	

COMPARE OPTIONS

3-Tab Asphalt Shingle

\$17,249

25-yr · 3-tab asphalt

Architectural Laminate

\$20,633

30-yr · architectural laminate

Designer / Impact-Resistant

\$25,781

Lifetime · designer / impact-resistant

Estimate notes. Pricing reflects 3,057 sqft of roof area at 4:12 pitch (30.57 squares). Estimate valid for 30 days from the date issued. Final pricing subject to inspection at framing if any unforeseen conditions are discovered. Permits, dumpster, and disposal included where required by local code.
Warranty: tier-dependent (see manufacturer documentation). **Payment:** 30% on contract signing, 60% at material delivery, 10% at completion.

CUSTOMER SIGNATURE · DATE

APEX AUTHORIZED · DATE